

ADDENDUM NO. 1


ROUNABOUT PROJECT 546007
STATE PROJECT STTP 5214(3) CONTROL NUMBER 12674
SPEC. NO. 04-056
40TH & SHERIDAN BLVD.

TO ALL PROSPECTIVE BIDDERS:

1. Please Remove and Replace Revised Bid Sheet Pages 6 and 7.
2. Plan Sheet No 2 the Summary of Quantities will be reissued to the successful low bidder with the change of pavement markings from preformed plastic to the painting shown.
3. Include the Special Provision for Detectable Warning Panels (Truncated Domes)

NOTE: Bidders are instructed to sign and fax this page of Addendum No. 21 back to the City of Lincoln Engineering Services, attention Mary Lowe at fax number 402-441-6576, as evidence that this Addendum No. 1 has been received and also staple this page to the front cover of your bid proposal book. Failure to do so could result in rejection of your bid.

Company/Contact Person



SPECIAL PROVISION FOR THE DETECTABLE WARNING PANELS (TRUNCATED DOMES)

A. GENERAL

The work covered by this Special Provision shall consist of all labor, materials, and equipment necessary for furnishing and installing Detectable Warning Panels (Truncated Domes).

1. The preformed tiles shall be Armor Tile's Cast-In-Place, as manufactured by Engineered Plastics, Inc.; Cast in Tact Warning Panels as manufactured by Mason's Supply Company; or as approved by the Engineer to be an equal.
2. Local representatives of these products include Larry Murray of Kel-Welco (402-476-1984) for the Armor Tile, and Jim Witt of Logan's Contractor's Supply (800-211-0177) for the Cast In Tact.

B. INSTALLATION

1. The Contractor shall furnish and install preformed tiles with Detectable Warning Panels (Truncated Domes) at all locations shown on the drawings or as directed by the Engineer, including but not limited to curb ramps, median crossings, railroad crossings and edge drop offs next to water. Location of installation shall be determined by Lincoln Standard Plan 600 and as approved by engineer.
2. This shall include all work associated with the installation of the preformed tiles in fresh concrete in accordance with the manufacturer's recommendations.
3. The Detectable Warning Panels shall be placed at the curb end of the ramps shown on the project plans. The surface to receive the Detectable Warning Panels shall be prepared to a smooth condition free of obstructions, depressions and debris. The contractor shall be required to furnish and install panels according to manufacturer's specification.

C. METHOD OF MEASUREMENT AND BASIS OF PAYMENT

1. Detectable Warning Panels, in place and accepted by the Engineer, shall be measured and paid for at the contract unit price bid per Square Foot for **DETECTABLE WARNING PANELS**.
2. Such payment shall be full compensation for furnishing all labor, equipment, materials and incidentals required to install the truncated domes as shown on the plans and as stipulated in these special provisions.
3. All costs of materials, labor and equipment for furnishing and placing Detectable Warning Panels shall be considered subsidiary to the cost of Detectable Warning Panels.

Schedule of Items

Contract ID: 546007 Project(s):
Letting Date: 03-10-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0200	23.0546 6" X 45 Deg. Bend, M.J.	Ea. 4.000				
0205	22.0780 Remove Sanitary Sewer Manhole (Complete)	Ea. 1.000				
0210	22.0700 Standard Manhole, Type "S"	Ea. 1.000				
0215	32.0040 Synthetic Fabric Silt Fence Installation	L.F. 500.000				
0220	32.0050 Synthetic Fabric Silt Fence Maintenance	L.F. 125.000				
0225	32.0060 Synthetic Fabric Silt Fence Removal	L.F. 500.000				
0230	50.0005 Misc. Paint Marking Yellow 6"	L.F. 682.000				
0235	50.0005 Misc. Paint Marking 6" White	L.F. 137.000				
0240	13.0305 Paint Marking, 12" White	L.F. 57.000				
0245	13.0270 Paint Marking, 4" Yellow	L.F. 307.000				

Date: 02-11-04

Revised: 03-02-04

Schedule of Items

Contract ID: 546007 Project(s):
 Letting Date: 03-10-04 Call Order: 001

Bidder:

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0250	50.0005 Misc. Paint Marking 18" White	240.000 L.F.				
0255	50.0001 Misc. Paint Marking, Sharks Teeth	20.000 Ea.				
0260	50.0001 Misc. Raised Pavement Markers	36.000 Ea.				
0265	50.0001 Misc. Install Round About Sign (W2-6)	4.000 Ea.				
0270	50.0001 Misc. Install Advisory Speed Limit Plaque (W13)	4.000 Ea.				
0275	50.0001 Misc. Install Yeild Sign (R1-2) with Street Na	4.000 Ea.				
0280	50.0001 Misc. Install One-Way Sign (R6-1)	4.000 Ea.				
0285	50.0001 Misc. Install Pedestrian Sign (W11-2)	8.000 Ea.				
0290	50.0001 Misc. Install Supplemental Plaque (W-16-7P)	8.000 Ea.				
0295	50.0001 Misc. Install No Parking Sign	4.000 Ea.				